

## TABLE OF CONTENTS

7.15	GEOLOGIC HAZARDS AND RESOURCES.....	7.15-1
7.15.1	AFFECTED ENVIRONMENT .....	7.15-1
7.15.1.1	Regional Geology .....	7.15-1
7.15.1.2	Regional Seismotectonic Setting and Seismicity .....	7.15-2
7.15.1.3	Local Geology .....	7.15-6
7.15.1.4	Geologic Hazards .....	7.15-8
7.15.1.5	Geologic Resources .....	7.15-10
7.15.2	ENVIRONMENTAL CONSEQUENCES .....	7.15-11
7.15.2.1	Proposed Project .....	7.15-11
7.15.2.2	Geologic Resources .....	7.15-12
7.15.3	CUMULATIVE IMPACTS.....	7.15-12
7.15.4	MITIGATION MEASURES .....	7.15-12
7.15.5	LAWS, ORDINANCES, REGULATIONS, AND STANDARDS .....	7.15-13
7.15.5.1	Federal .....	7.15-13
7.15.5.2	State .....	7.15-13
7.15.5.3	Local.....	7.15-13
7.15.6	INVOLVED AGENCIES AND AGENCY CONTACTS.....	7.15-13
7.15.7	PERMITS REQUIRED AND PERMIT SCHEDULE .....	7.15-13
7.15.8	REFERENCES .....	7.15-13

## TABLES

Table 7.15-1	Major Faults in WPGS Site Vicinity
Table 7.15-2	Applicable Geologic Laws, Ordinances, Regulations, and Standards
Table 7.15-3	Involved Agencies and Agency Contacts
Table 7.15-4	Required Permits

## FIGURES

Figure 7.15-1	Regional Geologic Map
Figure 7.15-2	Regional Seismicity Data
Figure 7.15-3	Mineral Resource Zones and Resource Sectors



## 7.15 GEOLOGIC HAZARDS AND RESOURCES

In accordance with California Energy Commission requirements, this section of the report presents information on the geological and tectonic setting of the region and site vicinity. Following this discussion, geologic hazards and resources are described to provide background information on the conditions surrounding the proposed Willow Pass Generating Station (WPGS) site. Unless specified otherwise, all discussions in this chapter referring to the WPGS site also refer to the project, which, by definition includes: (1) the WPGS plant itself; and (2) the water supply and discharge pipelines along an approximately 5-mile-long right-of-way connecting the WPGS with the Delta Diablo Sanitation District Wastewater Treatment Plant (DDSD WTP), the source of water for the project.

The discussion of geologic hazards includes surface fault rupture, strong ground shaking, liquefaction, mass wasting/slope stability, subsidence, and expansive soils. Potential impacts of the proposed project on the geologic resources at the site are also addressed. Based on this evaluation, measures are recommended to mitigate potential impacts from the proposed project.

The final portion of this section describes laws, ordinances, regulations, and standards (LORS) relevant to potential geologic impacts of the proposed project, and lists contacts in cognizant regulatory agencies. Required permits are also discussed.

### 7.15.1 Affected Environment

The WPGS site is at the northern end of the Diablo Range within the northern Coast Ranges physiographic province (Figure 7.15-1). This province is characterized by north-northwest-trending mountains and intervening valleys that extend from the Oregon border to the Transverse Ranges of southern California. The ridge and valley topographic character of the Coast Ranges province is predominantly controlled by the structural grain of the underlying geological units and subsequent erosion.

The WPGS site is on the southern side of Suisun Bay near the western edge of the Sacramento River delta. To the south, the Diablo Range's Los Medanos Hills reach elevations of about 1,300 feet. To the north of the site, the Sacramento River delta containing Chipps, Brown's, and Van Sickle Islands is at sea level, and many of the delta's islands are surrounded by manmade levees.

The WPGS site is underlain by fluvial/deltaic deposits of Pleistocene and Holocene age (Atwater, 1982). Recent topographic surveys of the site indicate that elevations within most of the WPGS site generally range from approximately 8 to 9 feet above mean sea level (msl). There are a few locations where elevations are lower, ranging from 5 to 8 feet, including the unused surface impoundment in the northernmost portion of the site and the drainage channel and surrounding area to the south of Tank 7 (see Figure 2.6-1). The highest existing grade on the WPGS site is at Tank 7, which is approximately 16 feet above msl. Other than this high point, the site is essentially flat, with topographic relief limited to slope faces along the shoreline, and around buildings, tanks, or other developed features.

#### 7.15.1.1 Regional Geology

The Coast Ranges represent northwest-southeast trending structural blocks comprising a variety of basement lithologies that are juxtaposed by major geologic structures. The Coast Ranges-Sierra Block (CRSB) boundary zone lies to the east of the site. To the west, the major boundary is the San Andreas fault zone, which separates Franciscan Complex rocks of the North American plate from the Salinian basement rocks on the Pacific plate. The Coast Ranges ophiolites within the Franciscan Complex have been deformed by a series of thrust faults, most of which appear to be inactive.

The Diablo Range, just south of the WPGS site, extends from the Sacramento River delta, south along the western side of the San Joaquin Valley. Rocks of the Mesozoic Great Valley sequence are thrust upon Franciscan basement along the San Joaquin Valley margin, and are covered locally by younger sediments of Paleocene to Pleistocene age.

Faults of the San Andreas system separate the Diablo Range from the remainder of the Coast Ranges. Mount Diablo is separated from the western East Bay Hills by the Calaveras fault and from the southern extension of the Diablo Range by the Livermore Valley, an east-west-trending Cenozoic basin. The Diablo Range is bounded to the east by the CRSB boundary zone, which typically is represented by a series of blind and partially concealed thrust faults (Wong et al., 1988; Unruh and Moores, 1992). The eastern side of Mount Diablo is bounded by the San Joaquin fault (Sowers et al., 1992).

The Diablo Range comprises a series of large en echelon anticlines, with intervening synclines. The anticlines are composed of Franciscan Complex rocks, while the synclines contain younger rocks. The folds are frequently cut by east- and west-verging thrust faults. These thrust faults are displaced or truncated by strike-slip movement on the northwest-striking, right-lateral faults of the San Andreas fault system.

### 7.15.1.2 Regional Seismotectonic Setting and Seismicity

As described above, the site lies within the broad San Andreas fault system, which accommodates the majority of the plate motion between the Pacific and North American plates. Although the most active faults within the system lie to the west of the site, active deformation related to the system also occurs in the site vicinity. Compressional tectonics reflected in the Coast Ranges also result in folds and thrusts subparallel to the San Andreas fault system.

#### Significant Faults

The most significant Quaternary faults within 50 miles of the WPGS site, and estimates of the maximum earthquake for each fault, are listed on Table 7.15-1. Maximum earthquake magnitude estimates are based on the Working Group on Northern California Earthquake Potential (WGNCEP) (WGNCEP, 1996). Table 7.15-1 also indicates the closest distance from each fault to the WPGS site.

Figure 7.15-2 illustrates the location of the WPGS site with respect to the major late-Quaternary faults in the site region. Fault data have been obtained from Bortugno et al. (1991), Jennings (1994), Unruh and Sawyer (1997), Simpson et al. (1992), Lienkaemper et al. (1991), and the WGNCEP (1996). The following describes each of the major faults listed in Table 7.15-1.

**San Andreas Fault.** The San Andreas fault is the largest active fault in California, extending from the Gulf of Mexico on the south approximately 750 miles to Cape Mendocino on the north. The San Andreas fault was the source of the 1906 Moment Magnitude ( $M_w$ ) 7.9 San Francisco earthquake (Wallace, 1990), which ruptured approximately 280 miles of the fault from San Juan Batista to Shelter Cove. The fault is about 40 miles west of the site at its closest approach.

The San Andreas fault can be divided into a number of segments, based on differences in geomorphology, geometry, paleoseismic chronology, seismicity, and historic displacements. In the Bay Area, these segments include the Southern Santa Cruz Mountains segment, possible source of the 1989  $M_w$  7.0 Loma Prieta earthquake; the Peninsula segment; and the North Coast segment. These segments have been assigned maximum earthquakes of  $M_w$  7,  $M_w$  7.1, and  $M_w$  7.9, respectively, by the WGNCEP (1996).

**Hayward Fault.** The Hayward fault is about 62 miles long and extends from Evergreen (east of San Jose) to Point Pinole, where it projects offshore into Suisun Bay. The fault demonstrates systematic right-

lateral creep offset of cultural features along its entire length (Lienkaemper et al., 1991). The October 1868 Local Magnitude ( $M_L$ ) 6.8 event was the last major earthquake to occur on the Hayward fault. The epicenter of this event was along the southern segment of the fault near Fremont.

The WGNCEP (1996) has divided the Hayward fault into two fault segments: a longer southern segment and a shorter northern segment. Based on the fault lengths associated with these segments and uncertainties in length measurements, maximum earthquakes of  $M_W$  6.9 have been assigned for both the northern and southern segments of the Hayward fault. The fault is located approximately 22 miles from the WPGS site. This structure is considered to be the most likely source of the next major earthquake in the San Francisco Bay area (Working Group on California Earthquake Probabilities [WGCEP], 1990).

**Concord-Green Valley Fault System.** The Concord-Green Valley fault is a northwest-striking, right-lateral strike-slip fault zone that extends about 33 miles from the Walnut Creek area across Suisun Bay to the north. The Concord segment extends approximately 12 miles, from the northern slopes of Mount Diablo to Suisun Bay. North of Suisun Bay, the Green Valley fault continues to the north for about 28 miles. The Concord fault is an actively creeping structure that has a long-term creep rate of approximately 5 millimeters per year (mm/yr). Recent investigations yielded geological evidence of previous large surface fault rupturing events.

Based on the length of the combined Concord and Green Valley fault segments, geometry, and previous rupture history, an earthquake involving both fault segments would produce a maximum earthquake of about  $M_W$  6.9 with a recurrence interval of approximately 180 years (WGNCEP, 1996). At its closest point, the Concord fault is about 11.5 miles from the WPGS site.

**Calaveras Fault.** The Calaveras fault represents a significant seismic source in the southern and eastern San Francisco Bay region. It extends from an intersection with the Paicines fault south of Hollister, through the Diablo Range east of San Jose, and along the Pleasanton-Dublin-San Ramon urban corridor. The fault consists of three major sections: the 15-mile-long southern Calaveras fault (from the Paicines fault to San Felipe Lake), the 38-mile-long central Calaveras fault (from San Felipe Lake to Calaveras Reservoir), and the 24-mile-long northern Calaveras fault (from Calaveras Reservoir to Danville). The poorly constrained slip rate on the southern section is interpreted to be  $15 \pm 2$  mm/yr, although some workers have postulated rates as high as 19 or 20 mm/yr. The central and northern sections have geologic slip rates of  $14 \pm 5$  mm/yr and  $6 \pm 2$  mm/yr, respectively. The level of contemporary seismicity along the southern section is low to moderate, whereas the central section has generated numerous moderate earthquakes in historic time. The northern section has a relatively low level of seismicity and may be locked. Geologic and seismologic data suggest that the northern section may produce earthquakes as large as  $M_W$  7.0. Paleoseismologic studies suggest a recurrence interval for large ruptures of between 250 and 850 years on the northern fault section. The timing of the most recent rupture on the northern Calaveras fault is unknown, but may be several hundred years ago (Kelson, 1999).

The WGNCEP (1996) estimated a maximum earthquake of  $M_W$  7.0 for the northern Calaveras fault. This section of the fault is located approximately 13 miles to the southwest of the WPGS site.

**Greenville-Clayton Fault.** The Greenville-Clayton fault is a northwest-striking strike-slip fault on the eastern side of the Diablo Range. The fault extends about 45 miles from Bear Valley to just north of the Livermore Valley. This fault has a lower slip rate than other structures within the San Andreas system, with a long-term rate of approximately 1 to 3 mm/yr. However, this fault produced a moderate magnitude earthquake in 1980 that caused minor surface fault rupture and damage to Interstate 580 east of Livermore, as well as damage to the Livermore Valley area.

Research is currently being conducted on the fault zone to better define its slip rate and its history of past earthquakes. The WGNCEP (1996) assigned a maximum earthquake of  $M_w$  6.9 to the Greenville fault; the recurrence interval is estimated to be about 550 years. The fault is located about 5.5 miles southwest of the WPGS site.

**Rodgers Creek Fault.** The Rodgers Creek fault is a 28-mile-long northwest-striking, right-lateral strike-slip fault that extends northward from the projection of the Hayward fault on the south side of San Pablo Bay. The Rodgers Creek has a similar long-term geological slip rate to the Hayward fault and has also produced a large magnitude historical earthquake in the late 1800s. Marine geophysical evidence suggests that the Hayward and Rodgers Creek faults are connected by a series of normal faults that extend across a 3-mile right step beneath San Pablo Bay. Current research suggests a low probability for the two faults to connect across this step-over during a large earthquake; instead, they are more likely to behave as separate structures. Paleoseismic investigations by Schwartz et al. (1992) identified evidence for three earthquakes in the last 925 to 1,000 years, yielding a preferred earthquake recurrence interval of 230 years for an  $M_w$  7.0 earthquake. The fault is about 29 miles from the WPGS site. The WGNCEP (1996) has assigned a maximum earthquake magnitude of  $M_w$  7.0 to the Rodgers Creek fault.

**West Napa Fault.** The West Napa fault consists of a north-northwest-striking zone of short right-lateral strike-slip fault segments in the hills to the west of the city of Napa (Bryant, 1982). The fault extends about 19 miles from Napa to Yountville. It is characterized by well-defined active fault features such as tonal lineations, scarps in late Pleistocene and Holocene alluvium, closed depressions, and right-laterally deflected drainages. The WGNCEP (1996) has assigned a maximum earthquake of  $M_w$  6.5 for the West Napa fault based on fault length and continuity. The fault is located approximately 22 miles to the northwest of the WPGS site.

**Coast Range-Sierran Block Boundary Zone.** The CRSB boundary zone consists of a complex zone of thrust faulting, marking the boundary between the Coast Ranges block and the Sierran basement rocks concealed beneath the Great Valley sedimentary sequence of the Sacramento and San Joaquin valleys. The basal detachment within the CRSB boundary zone is a low-angle, west-dipping thrust accommodating eastward thrusting of the Coast Range block over the Sierran block. Above this detachment is a complex array of west-dipping thrusts and east-dipping back-thrusts. The CRSB extends from near Red Bluff in the northern Sacramento Valley to Wheeler Ridge in the southern San Joaquin Valley (Wong et al., 1988; Wakabayashi and Smith, 1994).

The CRSB boundary zone was the probable source of the two  $M_w$   $6\frac{1}{4}$  to  $6\frac{3}{4}$  earthquakes recorded in 1892 near Winters, and the 1983  $M_w$  6.5 Coalinga earthquake in the western San Joaquin Valley (Wong et al., 1988). Although the faults themselves do not have surface expression, the CRSB boundary zone is marked by an alignment of fault-propagation folds such as the Rumsey Hills along much of its length (Unruh and Moores, 1992). Empirical relationships between fault length and earthquake magnitude suggest that these segments of the CRSB are capable of generating maximum earthquakes of  $M_w$  6.5 to 6.75, with an average recurrence interval of 360 to 440 years (Wakabayashi and Smith, 1994). The CRSB boundary zone is located about 11 miles from the WPGS site.

**Pittsburg-Kirby Hills Fault.** The Pittsburg-Kirby Hills fault (PKHF) extends a distance of approximately 26 miles from the Kirby Hills north of the Sacramento River, to the eastern flank of Mount Diablo, south of Pittsburg. Unruh et al., (1997) suggest that the structure is a right-lateral tear fault bounding the eastern margin of a series of thrusts and folds in the Grizzly Bay-Van Sickle Island area. The fault is defined by a linear alignment of microseismicity, which is unusual in that it occurs at depths of 20 to 25 kilometers (Wong et al., 1988). Focal mechanisms indicate that the movement on the fault is almost pure right-lateral strike-slip. Empirical relationships among various fault parameters and earthquake magnitude indicate that the maximum earthquake for the PKHF is  $M_w$  6.75 (Wells and

Coppersmith, 1994). Based on a projection of subsurface data, the fault zone is located within about 500 feet southwest of the WPGS site and crosses the water pipeline alignment within the Pittsburg Power Plant (PPP) site.

It should be noted that, although the PKHF is a known seismogenic structure, it is not included in the regional tectonic model used to predict future earthquake activity in the San Francisco Bay Area (WGCEP, 1999, 2003). This is because the model only includes fault structures with a demonstrated slip rate of  $\geq 1$  mm/yr and the PKHF does not meet this criterion. Furthermore, recent trenching studies conducted within the City of Pittsburg (TERRASEARCH, Inc., 2005) failed to verify the "Pittsburg" fault in the near subsurface. Accordingly, this fault structure has been removed from the City of Pittsburg's Health and Safety Element to the General Plan (City of Pittsburg, 2001).

**Mount Diablo Thrust.** The Mount Diablo thrust fault is a northeast-dipping structure located beneath the Mount Diablo anticline approximately 6 miles from the WPGS site. Unruh and Sawyer (1995) proposed that slip on the northern Greenville fault appears to die out northward because the fault steps to the northwest (left) across Mount Diablo to join with the right-lateral Concord fault. This implies that Mount Diablo is an asymmetric, southwest-vergent fault-propagation fold underlain by a northeast-dipping blind thrust fault that links the northern Greenville fault to the Concord fault.

Unruh and Sawyer (1997) estimated long-term average Quaternary shortening rates across the Mount Diablo region, from balanced cross sections, to be  $3.4 \pm 0.9$  mm/yr. Taking into consideration the presumed fault geometry, an average slip rate for the Mount Diablo thrust is calculated to be approximately  $4.1 \pm 1.4$  mm/yr. This blind thrust fault is judged capable of generating a maximum earthquake of  $M_w$  6.25.

**Antioch Fault.** The Antioch fault, about 3.5 miles east of the WPGS site, was previously considered active and was zoned under the Alquist-Priolo (AP) Act as potentially capable of surface rupture. A recent study by Wills (1992) indicates that the Antioch fault is not active and does not pose a surface-faulting hazard. The fault is no longer zoned by the State of California as an earthquake fault zone under the AP Act. Therefore, it is not listed on Table 7.15-1.

### Historical Seismicity

The historical seismicity for the San Francisco Bay region is largely associated with the San Andreas, Hayward, Rodgers Creek, Concord-Green Valley, PKHF, Calaveras, and Greenville faults (see Significant Faults, above). Several of these structures have produced large-magnitude historical earthquakes that caused damage to buildings and structures in the Bay Area. As a number of the earthquakes occurred before modern instruments were developed, the magnitude and distribution of damage can only be surmised from written historical documents. The earliest accounts of earthquakes in the San Francisco Bay Area were written in the 1800s, frequently in the logs of the Spanish missions.

### Significant Earthquakes

There have been 14 historical earthquakes of Magnitude (M) 6.0 or greater in the San Francisco Bay region (Figure 7.15-2). Earthquakes of this magnitude can pose significant ground-shaking hazard to the project area. The following paragraphs discuss several of these significant historic earthquakes that are considered of relevance to the WPGS site.

**May 19, 1889.** Of the historic earthquakes of M 6.0 or greater in the San Francisco Bay Area, this earthquake occurred closest to the WPGS site. This event may have been associated with the PKHF (see Significant Faults, above). Many chimneys toppled in Antioch and two small fissures were reported on

Main Street. Topozada et al. (1981) estimated the magnitude of the earthquake to be  $M_L 6$ , while Ellsworth (1990) assigned a  $M 6\frac{1}{4}$ .

**April 19 and 21, 1892.** This pair of earthquakes occurred within the CRSB on the western side of the Sacramento Valley (Wong et al., 1988; Unruh and Moores, 1992), causing extensive damage in Winters, Dixon, and Vacaville (Figure 7.15-2). The maximum reported intensities for both events was Modified Mercalli Intensity (MMI) IX, and the magnitudes have been estimated at  $M_L 6\frac{3}{4}$  to 7, and  $6\frac{1}{2}$  to  $6\frac{3}{4}$ , respectively (Wong et al., 1988). It is not clear whether surface faulting accompanied these events.

**March 31, 1898.** On March 31, 1898, the San Francisco Bay region experienced an earthquake that appeared to be centered near Mare Island at the north end of San Pablo Bay. A maximum intensity of MMI VIII or greater was reported, and buildings throughout the Bay Area were damaged. Topozada et al. (1992) have compared this event with other historical earthquakes and have assigned a magnitude of  $M_L 6.7$ .

**April 18, 1906.** The Great San Francisco earthquake of 1906,  $M_W 7.9$ , centered near Olema, was the most destructive earthquake to have occurred in northern California in historical times. Its effects were felt from southern Oregon to south of Los Angeles, and as far east as central Nevada. Damage from shaking was widespread in northern California and was most severe in areas of saturated or loose, young soils.

**October 17, 1989.** The  $M_W 7.0$  Loma Prieta earthquake occurred on or adjacent to the southern Santa Cruz Mountains segment of the San Andreas fault, severely damaging the cities of Los Gatos, Watsonville, Santa Cruz, San Francisco, and Oakland. Shaking was felt as far south as San Diego and as far east as Nevada. Similar to the 1906 San Francisco earthquake, the worst shaking damage occurred to buildings on unconsolidated or saturated soils, or with unreinforced masonry or improperly designed structures.

### 7.15.1.3 Local Geology

The surficial geology in the vicinity of the WPGS site is composed of late Tertiary sedimentary deposits in the southernmost portion of the 2-mile radius, while the remainder of the site area is composed entirely of late Quaternary to Holocene alluvial deposits and recent artificial fill (Figure 7.15-1). The geologic units were formed as a result of deposition of sediments from the San Joaquin River to the east, wind-blown transport of fine-grained silts and sand, and local drainages originating from the Diablo Range to the south.

#### Structure

The WPGS site is located within the “Mount Diablo fold and thrust belt” of Unruh and Sawyer (1995) at the northern end of the Diablo Range. The faults of the San Andreas system strike north-northwest, while the folds and thrust faults strike approximately east-west to northwest-southeast. The folds are closely related to the thrust faults because movement on the thrusts causes the formation of folds in the overlying strata. This fold and thrust belt is bounded by the PKHF to the east and the Potrero Hills thrust to the north. Movement on the Potrero Hills thrust and other thrusts has resulted in the formation of the Potrero Hills and Kirby Hills anticlines, as well as Honker Bay-Van Sickle Island, Los Medanos, and Concord anticlines. These anticlines are cut by several relatively short northeast-striking tear faults. This series of folds and thrusts is bounded to the south and west by the right-lateral Concord fault. The folds within this area plunge both to the east and the west, forming domes or structural traps for hydrocarbons within the Concord, Los Medanos, and Honker Bay-Van Sickle Island oil and gas fields.

## **Stratigraphy**

The stratigraphy beneath the PPP site comprises alluvial sediments of Suisun Bay; no bedrock occurs at the site. Historic artificial fills and levee fills are located on the PPP site locally and along Suisun Bay, respectively. In the 2-mile area around the PPP site, the stratigraphy includes, from oldest to youngest, Cenozoic sedimentary rocks, Quaternary sediments, Holocene sediments, and artificial fill as shown on Figure 7.15-1 and described below.

### **Cenozoic Deposits**

As shown on the regional geology map, Figure 7.15-1, the Cenozoic sedimentary section trends in a west-northwest to east-southeast direction across the foothills to the southwest of the WPGS site, and dips toward the northeast. The sedimentary units are described in the following paragraphs, from youngest to oldest (Sims, et al., 1973).

#### **Tehama Formation**

The Pliocene Tehama formation (Tpth) was formerly known as the Wolfshill formation and consists of sand, gravel, silt, and silty clay with irregularly interstratified volcanoclastic gravels.

#### **Lawlor Tuff**

This Pliocene unit (Tpl) is a pumiceous andesitic tuff-an airborne deposit.

#### **Neroly Sandstone**

This Miocene unit (Tmn) consists of tuffaceous pebbly crossbedded sandstone with conglomeratic lenses.

#### **Cierbo Sandstone**

The slightly older Miocene Cierbo sandstone (Tmci) is fine to coarse grained sandstone with concretionary medium grained sandstone in its upper part.

#### **Kreyenhagen Formation**

In this area, the Eocene aged deposit consists of the Markley sandstone member (Tem), a massive medium to coarse grained micaceous unit overlying the Upper sandstone unit (Tems) which is an interbedded sandy carbonaceous shale and sandstone.

### **Quaternary Alluvial Fan and Fluvial Deposits**

The unconsolidated quaternary alluvial fan and fluvial deposits are divided by Helley and Graymer (1997) into older Pleistocene and younger Holocene units. Alluvial fans and fluvial deposits of Pleistocene age consist of brown dense gravelly and clayey sand or clayey gravel that fines upward to sandy clay. They are distinguished from younger alluvial fans and fluvial deposits by higher topographic position, greater degree of dissection, and development of a more extensive soil profile. They are overlain by Holocene deposits on lower parts of the alluvial plain, and incised by channels that are partly filled with Holocene alluvium on higher parts of the alluvial plain.

As noted on Figure 7.15-1, approximately 3 miles of the 5-mile-long water supply/discharge pipeline alignment are underlain by this unit.

## **Holocene Deposits**

Alluvial fan and fluvial deposits of Holocene age are predominantly brown or tan, medium dense to dense, gravelly sand or sandy gravel that generally grades upward to sandy or silty clay. As noted on Figure 7.15-1, the proposed water pipeline alignment is underlain by this unit for about 1,000 linear feet, from west of Harbor Street to Elm Street.

## **Historic Artificial Fills**

A series of manmade fills has been placed in the vicinity of the PPP site over the years to increase the surface grade and provide more stable ground for industrial development. The lithologies of the numerous fills have varied with time but are generally believed to be relatively coarse-grained (e.g., sands and gravels), rather than finer materials (e.g., silts and clays).

As noted on Figure 7.15-1, some of the fills have been used to create artificial levees surrounding discrete geographic areas, including streams. The levee fills tend to be finer grained than the broad area fills. Approximately 0.8 mile of the proposed water pipeline alignment in the vicinity of the PPP is underlain by artificial fills, as indicated on Figure 7.15-1.

### **7.15.1.4 Geologic Hazards**

The following paragraphs discuss potential geologic hazards that may occur relative to the project at the WPGS site and its associated pipelines.

#### **Surface Fault Rupture**

No active or potentially active faults are mapped on the WPGS site. The closest fault zone to the site zoned under the AP Earthquake Fault Zoning Act is the Greenville-Clayton fault, about 3.5 miles to the southwest. The AP Act requires the California Geological Survey to designate faults considered active or potentially active, and establishes zones within which studies are required for structures involving human occupancy. All of the faults discussed in Significant Faults, above, are shown on Table 7.15-1 except the PKHF, the CRSB, the West Napa fault, and the Mount Diablo thrust are zoned in accordance with the AP Act. Based on the lack of geomorphic expression of active faulting and the absence of AP-zoned faults in the WPGS area, the hazard from ground rupture is considered negligible.

#### **Earthquake Ground Shaking**

Strong ground shaking due to future seismic events is probably the most significant geologic hazard anticipated at the WPGS site. The site has experienced strong ground motions in the past and will do so in the future. Based on the USGS Seismic Hazard Mapping Program (Petersen, et al., 2008), bedrock ground motions with a 10 percent probability of being exceeded within the next 50 years are estimated at 0.4 g.

#### **Liquefaction**

Liquefaction is the phenomenon during which loose, saturated, cohesionless soils temporarily lose shear strength during strong ground shaking. Significant factors known to affect the liquefaction potential of soils are the characteristics of the materials such as grain size distribution, relative density, degree of saturation, the initial stresses acting on the soils, and the characteristics of the earthquake, such as the intensity and duration of the ground shaking.

Potential hazards at the WPGS site include compaction consolidation (settlement) and seismically induced settlement. Dissipation of excess pore pressure generated by ground shaking would produce volume changes within the liquefied soil layers, which would be manifested at the ground surface as settlement.

A review of more than 60 geotechnical borings drilled for Pacific Gas and Electric Company in the northeastern portion of the PPP site by Dames & Moore (1951, 1952, 1953, 1968), a predecessor company, indicates the following:

- More than 20 borings were drilled in the WPGS site area, with total depths of 31 to 91 feet.
- Of these, on the order of 15 were drilled in the approximate proposed power block area.
- By far, the most borings were drilled using cable tool and mud rotary drill rigs in the 1950s and logged using an old Tripartite Soil Classification system in lieu of the currently used Unified Soil Classification System.
- None of these earlier boring logs included blow counts. Liquefaction susceptibility based on blow count data is therefore not possible at the drilled locations.

Nevertheless, the existing subsurface data are suitable for assessing general geologic/geotechnical conditions for the purposes of the AFC.

### **Mass Wasting and Slope Stability**

The WPGS site and associated water pipeline alignment are on a flat alluvial plain, approximately 2.5 miles north of the Mount Diablo range-front. The lack of significant slopes on or near the site indicates that the hazard from slope instability, both landslides and debris flows, is negligible.

The WPGS site is immediately adjacent to Suisun Bay. Erosion may therefore pose a hazard to the plant area. However, stream bank protection appears to control or mitigate this hazard. Drainage on and around the site is controlled by a series of flood control drains; therefore, the hazard of erosion from surface runoff is also considered to be negligible.

### **Subsidence**

Subsidence of the land surface can be attributed to natural phenomena, such as tectonic deformation, consolidation, hydrocompaction, collapse of underground cavities, oxidation of organic-rich soils, or rapid sedimentation, and also by the activities of man, such as the withdrawal of groundwater or hydrocarbons. Most of the physical conditions responsible for areal land subsidence are not known to exist at the WPGS site. Subsidence caused by groundwater withdrawals is not expected to be a significant problem at the WPGS site; however, future changes in groundwater pumping or development of hydrocarbon reserves in the Sacramento Delta could theoretically impact the site.

### **Expansive Soils**

All of the WPGS site is underlain by soil identified as Clear Lake Clay (on 2 to 9 percent slopes), characterized by poor drainage and high shrink-swell potential (Welch, 1977).

Approximately 55 percent of the water pipeline alignment is underlain by Capay clay and Brentwood clay loam, (Figure 7.9-1) both of which exhibit high shrink-swell potential (Welch, 1977). Although

this could be a factor with respect to foundation support of shallow footings, it is not anticipated to be relevant to a buried pipeline.

### **Tsunami and Seiche**

Tsunami (commonly, but mistakenly, called tidal waves) are sea waves caused by submarine fault movements or landslides. The WPGS site is not known to have experienced tsunamis in the historic past, and the U.S. Geological Survey estimates, based on records from 1960 and 1964 events, that attenuation results in a reduction of the wave height measured at the Golden Gate by 90 percent by the time it reached the vicinity of Carquinez Strait (Ritter and Dupre, 1972).

Recent studies (Borrero, Dengler, Uslu and Synolakis, 2006) suggest that the maximum tsunami anticipated for San Francisco Bay would be generated by a M 9.2 earthquake in the Aleutian Islands, a return period of approximately 500 years. This event would result in a calculated wave of 5.4 meters (m) at the Golden Gate, diminishing to 0.54 m ( $\pm 1.6$  feet) at the Carquinez Strait. For example the 1964 Alaskan earthquake generated a wave 2.6-m-high at the Golden Gate, decreasing to 0.37 m ( $\pm 1.1$  feet) at Carquinez Strait. Because the WPGS is over 25 miles upriver from the Carquinez Strait the maximum anticipated wave would be several inches high, thus, tsunami is not considered a hazard to the WPGS site.

Seiches result from the “sloshing” action of confined bodies of water during seismic events. Because no such bodies of water are present at the WPGS site, seiche is not considered to be a hazard.

#### **7.15.1.5 Geologic Resources**

The following geologic resources are found in the vicinity of the WPGS site.

### **Sand and Gravel Aggregate Resources**

In 1987, the CDMG published a comprehensive mineral land classification for aggregate materials in the San Francisco-Monterey Bay Area (Stinson et al., 1987). Lands were classified in the following categories:

**MRZ-1:** Areas where adequate information indicates that no significant mineral deposits are present, or where it is judged that little likelihood exists for their presence.

**MRZ-2:** Areas where adequate information indicates that significant mineral deposits are present, or where it is judged that a high likelihood for their presence exists.

**MRZ-3:** Areas containing mineral deposits, the significance of which cannot be evaluated from available data.

According to these definitions, the entire vicinity of the WPGS is classified as MRZ-1. A map of mineral resource zones is shown on Figure 7.15-3. Sandstones of the Wolfskill Formation located in the hills about 3 miles south of the WPGS site have been identified as a source of non-Portland Cement Concrete aggregate.

### **Oil and Gas Resources**

The Sacramento River delta region contains a large number of small and medium-sized gas fields formed within Tertiary units by structural traps, typically faulted anticlines and domes. Several exploratory wells are located within several miles of the site. The closest proven hydrocarbon resources to the WPGS site are beneath Honker Bay, approximately 3 miles to the north-northwest, and the larger Rio Vista gas field

about 15 miles to the northeast (Bowen, 1962). There are no known hydrocarbon resources in the WPGS site.

## Mineral Resources

The Black Diamond Mines of the Mount Diablo Coalfield, the largest known and most extensively mined coal deposit in California (Sullivan and Waters, 1980), are located several miles to the south of the WPGS site. These subbituminous deposits were worked for almost 50 years, from the 1860s to the early part of the 1900s. The coal seams are located within the upper Domengine Formation and at the top of the Lower Domengine (Sullivan et al., 1995). The coal seams are of relatively poor quality, consisting predominantly of lignite, with some subbituminous coal interbedded with fine-grained units. The estimated reserves remaining at Black Diamond are approximately 8 million tons. The poor quality of the remaining coal, however, precludes these reserves from being exploited as economic reserves in the near future.

### 7.15.2 Environmental Consequences

Significance criteria have been selected based on California Environmental Quality Act Guidelines (Appendix G, Environmental Checklist Form) as well as performance standards adopted by responsible agencies. An impact may be considered significant from a geologic standpoint if the project results in:

- Severe damage or destruction of any project component, release of a toxic or other hazardous substance into the environment, or exposure of people or property to substantial adverse effects as the direct consequence of a geologic event; for example:
  - Earthquake fault rupture
  - Strong ground shaking during a seismic event
  - Seismically induced ground failure such as liquefaction and/ or lateral spreading
  - Subsidence
  - Expansive soils
  - Mass wasting, landslides, rockfalls, or other slope failures
  - Inundation by seiche or tsunami; or
- Loss of availability of a known mineral source classified MRZ-2 by the State Geologist or a locally important mineral resource site.

#### 7.15.2.1 Proposed Project

##### Geologic Hazards

Seismically induced ground shaking presents a significant hazard to the project. The potential for liquefaction during future seismic events is also considered to be locally high at the plant site. The native soils beneath the WPGS project site do not have a potential for undergoing shrink-swell behavior. With incorporation of the project design features discussed in Section 7.15.4, the hazards will be reduced to an acceptable level. No other geologic hazards with the potential to significantly affect the WPGS or other project elements were identified.

##### Geologic Conditions and Topography

Potential impacts of the proposed project on the geologic environment can be divided into those involving construction activities and those related to plant operation. Construction-related impacts to the geologic

environment primarily involve terrain modifications including cuts, fills, and dust generation. Most of the WPGS site is relatively flat at around 8 to 9 feet (msl) and is currently occupied by existing Tank 7 and PPP Units 1 through 4. The proposed grading plan indicates an estimated cut of about 8,300 cubic yards (cy) and an estimated fill of 83,800 cy to achieve a plant site elevation ranging from 8 to 13 feet (msl). Thus, fills could be on the order of 3 to 5 feet thick (see Figure 2.6-2). Site grading is not expected to result in significant adverse impacts to the geologic environment. No significant adverse impacts on the geologic environment are expected from the construction or operation of the proposed project.

### **7.15.2.2 Geologic Resources**

Natural resources occurring within the vicinity of the WPGS site include sand, gravel, natural gas, and coal (lignite and subbituminous coal). All of these resources have been exploited to some extent in the site vicinity, but with the exception of natural gas, no active development operations are occurring at this time. No significant impacts on geologic resources would occur as a result of the construction or operation of the project.

### **7.15.3 Cumulative Impacts**

No cumulative impacts are anticipated to the geologic environment as a result of the WPGS.

### **7.15.4 Mitigation Measures**

The following sections describe mitigation measures that might be employed to reduce potential significant geologic hazards to acceptable levels.

#### **GEO-1 Seismic Design Requirements**

The power plant may be subjected to strong earthquake motions in the future. Thus, plant components must be designed and constructed to the seismic design requirements for ground shaking specified in the International Building Code for Seismic Design Category D.

#### **GEO-2 Geotechnical Investigation**

The hazard from seismically induced liquefaction at the plant area is considered to be locally high. The nature of the alluvial and fluvial deposits on which the plant will be sited and the presence of potentially liquefiable materials indicates that liquefaction and lateral spreading could occur. Because of the location of new structures with respect to the existing geotechnical database, a site-specific program of exploratory borings and accompanying laboratory testing will be required to delineate potentially liquefiable materials beneath the construction area. These geotechnical investigations will also be required for consideration prior to foundation design and development of site-specific design criteria. These are normal design and construction techniques.

#### **GEO-3 Engineering Geologist**

Prior to the start of construction, the project owner shall assign to the project an engineering geologist(s), certified by the State of California, to carry out the duties required by the 2007 edition of the California Building Code (CBC) Appendix, Chapter 33, Section 3309.4. Engineered Grading Requirement and Section 3318.1 – Final Reports. Those duties are:

1. Prepare the Engineering Geology Report. This report shall accompany the Plans and Specifications when applying to the Chief Building Official for the grading permit.

2. Monitor geologic conditions during construction.
3. Prepare the Final Engineering Geology Report.

The certified engineering geologist(s) assigned must be approved by the Compliance Project Manager (CPM). The functions of the engineering geologist can be performed by the responsible geotechnical engineer, if that person has an appropriate California license.

### **7.15.5 Laws, Ordinances, Regulations, and Standards**

The proposed project will be constructed and operated in accordance with all LORS applicable to geologic hazards and resources. LORS relevant to this project are discussed in the following sections and shown on Table 7.15-2.

#### **7.15.5.1 Federal**

Acceptable design criteria for excavations and structures for static and dynamic loading conditions are specified by the International Building Code (IBC), 2007.

#### **7.15.5.2 State**

Given the nature of the project, the CBC (2007) would be superceded by the IBC as discussed above.

#### **7.15.5.3 Local**

Depending on the status of annexation, grading and building would be regulated by either Contra Costa County or the City of Pittsburg.

### **7.15.6 Involved Agencies and Agency Contacts**

Involved agencies and agency contacts are listed in Table 7.15-3.

### **7.15.7 Permits Required and Permit Schedule**

Required permits are listed in Table 7.15-4.

### **7.15.8 References**

- Atwater, B. F., 1982. Maps of the Sacramento-San Joaquin Delta, California. USGS Miscellaneous Field Studies Map MF-1401, Boulder, Colorado.
- Borrero, J., L. Dengler, B. Uslu, and C. Synolakis, 2006. Numerical modeling of tsunami effects at Marine Oil Terminals in San Francisco Bay, Report prepared for: Marine Facilities Division of the California State Lands Commission, June 8.
- Bortugno, E. J., R. D. McJunkin, and D. L. Wagner, 1991. Map showing recency of faulting, San Francisco-San Jose Quadrangle, California. California Division of Mines and Geology. Geologic Map of the San Francisco-San Jose Quadrangle, 1:250,000.
- Bowen, Oliver E., 1962. Geologic Guide to the Gas and Oil Fields of Northern California, California Division of Mines and Geology, Bulletin 181, Oliver E. Bowen Jr., Editor.

- Bryant, W. A., 1982. West Napa fault zone and Soda Creek (East Napa) fault. California Division of Mines and Geology. Fault Evaluation Report FER-129. 10 pp.
- CBC (California Building Code), 2007. International Code Council.
- City of Pittsburg, 2001. Health and Safety Element to the General Plan adopted November 2001, as amended by City Council Resolution No. 07-10779, May 21, 2007.
- Dames & Moore, 1951. Preliminary Foundation Investigation, Proposed Industrial Site, Near Pittsburg, California, for the Pacific Gas and Electric Company, Job No. 160-Z, September 4.
- Dames & Moore, 1952. Report of Foundation Investigation, Part I, Presentation of Data. Proposed Pittsburg Steam Plant, Pittsburg, California, for the Pacific Gas and Electric Company, Job No. 160-AC March 3.
- Dames & Moore, 1953. Report of Foundation Investigation, Part II, Analyses and Recommendations, Proposed Pittsburg Steam Plant, Pittsburg, California, for the Pacific Gas and Electric Company, Job No. 160-AC, May 26.
- Dames & Moore, 1968. Final Recommendations for Piling and Supplementary Field Investigation. Pittsburg Power Plant Unit 7 Pittsburg, California, for Pacific Gas and Electric Company, Job No. 160-130-03, October 29.
- Ellsworth, W. L., 1990. Earthquake History, 1769-1989. In R. E. Wallace, ed., *The San Andreas Fault System, California*. U.S. Geological Survey Professional Paper 1515. 1990. pp. 153-181.
- Graymer, R. W., D. L. Jones, and E. E. Brabb, 1994. Preliminary Geologic Map Emphasizing Bedrock Formations in Contra Costa County, California: A Digital Database. U.S. Geological Survey, Open Report 94-622.
- Helley, E. J. and R. W. Graymer, 1997. Quaternary geology of Contra Costa County, and surrounding parts of Alameda, Marin, Sonoma, Solano, Sacramento, and San Joaquin Counties, California: A digital database. U.S. Geological Survey, Open-File Report 97-98.
- IBC (International Building Code), 2006. International Code Council.
- Jennings, C. W., 1994. Fault activity map of California and adjacent areas. California Division of Mines and Geology. California Geologic Data Map Series, Map No. 6. 1:750,000 scale.
- Kelson, K., 1999. In Review. *Geologic characterizations of the Calaveras Fault as a potential seismic source*. Submitted to AEG Volume, Engineering geology in Northern California.
- Lienkaemper, J. J., G. Borchardt, and M. Lisowski, 1991. Historic creep rate and potential for seismic slip along the Hayward fault, California. *Journal of Geophysical Research*. 96B:18261-18283.
- Petersen, Mark D., Arthur D. Frankel, Stephen C. Harmsen, Charles S. Mueller, Kathleen M. Haller, Russell L. Wheeler, Robert L. Wesson, Yuehua Zeng, Oliver S. Boyd, David M. Perkins, Nicholas Luco, Edward H. Field, Chris J. Wills, and Kenneth S. Rukstales, 2008. Documentation for the 2008 Update of the United States National Seismic Hazard Maps: U.S. Geological Survey Open-File Report 2008-1128, 61 pp.
- Ritter, J. R. and W. R. Dupre, 1972. Map showing Areas of Potential Inundation by Tsunamis in the San Francisco Bay Region. U.S. Geological Survey. Miscellaneous Field Studies Map MF-480.

- Schwartz, D. P., D. Pantosti, S. Hecker, K. Okomura, K. E. Budding, and T. Powers, 1992. Late Holocene behavior and seismogenic potential of the Rodgers Creek fault zone. Sonoma County, California, in Proceedings of the Second Conference on Earthquake Hazards in the Eastern San Francisco Bay Area. Borchardt, G., S. E. Hirschfeld, J. J. Lienkaemper, P. McClellan, P. L. Williams, and I. G. Wong (eds.). California Department of Conservation, Division of Mines and Geology. pp. 393-398.
- Simpson, G. D., W. R. Lettis, and K. I. Kelson, 1992. Segmentation model for the northern Calaveras fault, Calaveras Reservoir to Walnut Creek, in Proceedings of the Second Conference on Earthquake Hazards in the Eastern San Francisco Bay Area. Borchardt, G., S. E. Hirschfeld, J. J. Lienkaemper, P. McClellan, P. L. Williams, and I. G. Wong (eds.). California Department of Conservation, Division of Mines and Geology. pp. 253-259.
- Sims, J.D., K.F. Fox Jr., J.A. Bartow, and E.J. Helley, 1973. Preliminary Geologic Map of Solano County and Parts of Napa, Contra Costa, Marin and Yolo Counties, California, U.S. Geological Survey Miscellaneous Field Studies Map MF-484.
- Sowers, J. M., J. S. Noller, and J. R. Unruh, 1992. Quaternary deformation and blind-thrust faulting on the east flank of the Diablo Range near Tracy, California. In Proceedings of the Second Conference on Earthquake Hazards in the Eastern San Francisco Bay Area. Borchardt, G., S. E. Hirschfeld, J. J. Lienkaemper, P. McClellan, P. L. Williams, and I. G. Wong (eds.). California Department of Conservation, Division of Mines and Geology. pp. 377-383.
- Stinson, M. C., M. W. Manson, and J. J. Plappert, 1987. Mineral land classification: Aggregate materials in the San Francisco-Monterey Bay area Part II Classification of aggregate resource areas South San Francisco Bay Production-Consumption Region. California Division of Mines and Geology. Special Report 146, Part 11. 74 pp.
- Sullivan, R., J. Waters and M.D. Sullivan, 1995. Geology and sequence stratigraphy of the Black Diamond Mines Regional Preserve. *Northern California Geological Society, Guidebook*.
- Sullivan, R. and J. Waters, 1980. Mount Diablo coalfield, Contra Costa County, California. *California Geology*. 33:51-59.
- TERRASEARCH, Inc., 2005. Fault Rupture Hazard Investigation, Mariner Walk Site, Herb White Way and 8th Avenue, Pittsburg, California, for The Olson Company, April 5.
- Topozada, T. R., C. R. Real, and D. L. Parke, 1981. Preparation of isoseismal maps and summaries of reported effects of the pre-1900 California earthquakes. California Division of Mines and Geology. Open-File Report 81-11, 181 pp.
- Topozada, T. R., J. H. Bennett, C. L. Hallstrom, and L. G. Youngs, 1992. 1898 "Mare Island" earthquake at the southern end of the Rodgers Creek fault., in G. Borchardt and others (eds.). Proceedings of the Second Conference on Earthquake Hazards in the Eastern San Francisco Bay Area. California Department of Conservation, Division of Mines and Geology Special Publication 113. pp. 385-392.
- Unruh, J. R. and E. M. Moores, 1992. Quaternary blind thrusting in the southwestern Sacramento Valley, California. *Tectonics*. 11: 192-2033.
- Unruh, J. R. and T. L. Sawyer, 1995. Late Cenozoic growth of the Mt. Diablo fold-and-thrust belt, central Contra Costa County, California, and implications for transpressional deformation of the northern Diablo Range. *American Association of Petroleum Geologists Bulletin*. 79:600.

- Unruh, J. R. and T. L. Sawyer, 1997. Assessment of blind seismogenic sources, Livermore Valley, eastern San Francisco Bay region. William Lettis and Associates, Final Report for U.S. Geological Survey National Earthquake Hazards Reduction Program Award Number 1434-95-G-2611. 95 pp.
- Unruh, J. R., S. T. Hector, P. L. Williams, and J. W. Rector, 1997. Transpressional tectonics of the western Sacramento-San Joaquin delta, eastern San Francisco Bay region, California. EOS, Transactions of the American Geophysical Union. v. 78. p. F63 1.
- URS (URS Corporation), 2001, Soils Engineering and Engineering Geology Report, Contra Costa Power Plant, Unit 8 Project, Contra Costa County, California, for Mirant Corporation, June 29.
- Wakabayashi, J. and D. L. Smith, 1994. Evaluation of recurrence intervals, characteristic earthquakes and slip-rates associated with thrusting along the Coast Range-Central Valley geomorphic boundary. Bulletin of the Seismological Society of America. 84:19604 970.
- Wallace, R. E., 1990. The San Andreas Fault System, California. U.S. Geological Survey Professional Paper 1515. 283 p.
- Welch, L. E., 1977. Soil Survey of Contra Costa County, California. U.S. Department of Agriculture, Soil Conservation Service. 125 pp.
- Wells, D. L. and Coppersmith, K. J., 1994. New empirical relationships among magnitude, rupture length, rupture width, rupture area, and surface displacement. Bulletin of the Seismological Society of America. v. 84. pp. 974-1002.
- WGCEP (Working Group on California Earthquake Probabilities), 1990. Probabilities of large earthquakes in the San Francisco Bay region, California. U.S. Geological Survey, Circular 1053. 51 pp.
- WGCEP (Working Group on California Earthquake Probabilities), 1999. Earthquake Probabilities in the San Francisco Bay Region: 2000 to 2030 – A Summary of Findings, U.S. Geological Survey, Open File Report 99-517.
- WGCEP (Working Group on California Earthquake Probabilities), 2003. Earthquake Probabilities in the San Francisco Bay Region: 2002 to 2031, U.S. Geological Survey Open File Report 03-214.
- WGNCEP (Working Group on Northern California Earthquake Potential), 1996. Database of potential sources for earthquakes larger than magnitude 6 in northern California. U.S. Geological Survey. Open-File Report 96-705. 53 p.
- Wills, C. J., 1992. The elusive Antioch fault, in Proceedings of the Second Conference on Earthquake Hazards in the Eastern San Francisco Bay Area. Borchardt, G., S. E. Hirschfeld, J. J. Lienkaemper, P. McClellan, P. L. Williams, and I. G. Wong (eds.). California Department of Conservation, Division of Mines and Geology. pp. 325-331.
- Wong, I. G., R. W. Ely, and A. C. Kollmann, 1988. Contemporary seismicity and tectonics of the Northern and Central Coast Ranges-Sierran Block Boundary zone, California. *Journal of Geophysical Research*. 93:7,813-7,833.




<b>Table 7.15-1 Major Faults in WPGS Site Vicinity</b>			
<b>Fault Name</b>	<b>Fault Segment Length (miles)</b>	<b>Horizontal Distance to WPGS Site (miles)</b>	<b>Maximum Magnitude <math>M_w</math></b>
San Andreas	280	40	7.9
Hayward	26	22	6.9
Concord-Green Valley	33.6	11.5	6.9
Calaveras	38	13	7.0
Greenville-Clayton	45	5.5	6.9
Rodgers Creek	42	29	7.0
West Napa	19	22	6.5
Coast Range-Sierra Block Boundary Zone	21	11	6.75
Pittsburg-Kirby Hills	26	0.01	6.75
Mount Diablo Thrust	~15	6	6.25
Source: WGNCEP (1996)			

<b>Table 7.15-2 Applicable Geologic Laws, Ordinances, Regulations, and Standards</b>			
<b>Laws, Ordinances, Regulations, and Standards</b>	<b>Applicability</b>	<b>Administering Agency</b>	<b>AFC Section</b>
<b>Federal</b>			
International Building Code (IBC), 2007	Design criteria for excavations and structures under static and dynamic loading conditions	City of Pittsburg	7.15.5.1
<b>State</b>			
California Building Code, 2001	Superseded by IBC	N/A	7.15.5.2
<b>Local</b>			
Contra Costa County General Plan Safety Element (2005)	Outlines policies and goals related to seismic ground failure and landslide hazards	Contra Costa County	7.15.5.3
City of Pittsburg General Plan (2001) Health and Safety Element	Outlines City objectives and policies related to Geology and Seismicity	City of Pittsburg	7.15.5.3


<b>Table 7.15-3 Involved Agencies and Agency Contacts</b>		
<b>Issue</b>	<b>Agency/Address</b>	<b>Telephone</b>
Geologic Resources	California Geological Survey Headquarters/Office of the State Geologist 801 K Street, MS 12-30 Sacramento, CA 95814 cgshq@consvr.ca.gov	(916) 445-1825 (916) 445-5718 fax
Building Code	City of Pittsburg, Building Division 65 Civic Avenue Pittsburg, CA 94565	Curtis Smith Chief Building Official, Building Division (925) 252-4910

<b>Table 7.15-4 Required Permits</b>		
<b>Responsible Agency</b>	<b>Permit/Approval</b>	<b>Schedule</b>
City of Pittsburg	Grading and Construction Permit	To be obtained before construction begins.




**LEGEND**

af	Artificial Fill (Historic)	Qls	Landslide deposits (Pleistocene and/or Holocene)		Strike and Dip of Bedding
alf	Artificial Levee Fill (Historic)	Qpaf	Alluvial Fans and Fluvial Deposits (Pleistocene)		Water
Qhaf	Alluvial Fan and Fluvial Deposits (Holocene)	QTu	Undifferentiated Continental Gravels (Plio-Pleistocene)		2-Mile Radius
Qhsc	Stream Channel Deposits (Holocene)	Tph	Tehama Formation		Offsite Water Supply and Discharge Pipeline Route
Qhb	Basin Deposits (Holocene)	Tmn	Neroly Sandstone		
Qhbm	Bay Mud (Holocene)	Tpl	Lawlor Tuff		
Qhl	Natural Levee Deposits (Holocene)	Tmci	Cierbo Sandstone		
Qhpm	Peat and Peaty mud (Holocene)	Tem	Kreyenhagen Formation Markley Sandstone Member		
Qhsc	Stream Channel Deposits (Holocene)	Tems	Kreyenhagen Formation Upper Sandstone Member		
Qds	Dune Sand (Pleistocene and Holocene)				



**REGIONAL GEOLOGIC MAP**  
 Willow Pass Generating Station  
 Mirant Willow Pass, LLC  
 Pittsburg, California  
 June 2008  
 28067343  
**URS**  
**FIGURE 7.15-1**

Sources: Quaternary Geology of Contra Costa County, and surrounding parts of Alameda, Marin, Sonoma, Solano, Sacramento, and San Joaquin Counties, California: A Digital Database. Compiled by Helley, E. J.; Graymer, R. W., 1997. Bedrock geology from Sims, et al., 1973. USGS Topographic 7.5-Minute Quadrangles: Antioch North (1978), Antioch South (1980), Clayton (1994), Honker Bay (1980)



**REGIONAL SEISMICITY DATA**


Willow Pass Generating Station  
 Mirant California, LLC  
 Pittsburg, California

June 2008  
 28067343




**FIGURE 7.15-2**

Source:  
 National Geophysical Data Center,  
 (NGDC), Boulder, CO



Source: USGS  
M.C. Stinson, M.W. Manson, and J.J. Plappert 1983

Map Number	Quadrangle
71	Honker Bay
72	Antioch North
82	Clayton
83	Antioch South



### MINERAL RESOURCE ZONES AND RESOURCE SECTORS

June 2008  
28067343

Willow Pass Generating Station  
Mirant California, LLC  
Pittsburg, California



FIGURE 7.15-3